

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50N N.R. 8W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Cor. common to Secs. 21-28

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-11-70

WITNESSES TO CORNER..... 9" Red Pine (¼S NBT) N65°W 46.3'



7" Red Pine (¼S NBT) S28° 9.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Squared and scribed 8" Red Pine, 1.4' North of corner.

This Cor. replaced from one original B.T.; a Y. Pine stub, bearing S78°E, 58 links. Stub is cut 4½" high. Both faces plain.

Cor. lies in North-East corner of a jack pine clearcut.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 9-23-70
REGISTERED LAND SURVEYOR