

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

3 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> ^{N.} S. , R. <u>8</u> ^{E.} W.	C-7A, C-7B
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>50</u> ^{N.} S. , R. <u>8</u> ^{E.} W.	D-7A
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-20, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-7A Meander Corner bet. Sec's. 17-18, set by Wells Burt, D.S. at record distance North of Sec. Cor. 17-18-19-20, 471.9' in 1850. Bearings were: W. Pine 9", S14¹/₂^{OW}, 47 lks. and W. Pine 12", S62^OE, 64 lks.

C-7B Meander Corner bet. Sec's. 18-19, set by Wells Burt, D.S. at record distance West of Sec. Cor. 17-18-19-20, 735.9' in 1850. Bearings were: Y. Pine 10", S58^OE, 44 lks. and W. Pine 10", S2^OE, 38¹/₂ lks.

D-7A Meander Corner on the North-South ¹/₂ line, Section 17.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-7A Placed corner 145.8' North of Sec. Cor. 17-18-19-20, by extending Section Line bearing bet. Sec's. 19-20.

C-7B Placed corner monument, 104.0' West of Sec. Cor. 17-18-19-20, by extending Section Line Bearing bet. Sec's. 17-20.

D-7A Placed corner on mean bearing bet. East and West sides of Section 17, and 1650.2' North of the South ¹/₂ corner of Section 17.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at all three corners. New Bearings:

C-7A 18" Red Pine, N81^OE, 62.5' & 14" Soft Maple, S12^OW, 53.7'. Corner placed 25' South of high eroded bank, 110' above Lake Superior.

C-7B 6" Oak, S78^OE, 12.2' & 8" Red Pine, S2^OE, 27.0'.

D-7A 12" Red Pine, S73^OW, 9.0' & 8" W. Pine, S79^OE, 15.0'. Placed corner 117.0' back from high bank of Lake Superior.

SIGNED BY Billy D. Buckler DATE 8-21-80
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET