

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

4 Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. _____ N. S., R. _____ E. W.	9-Sec.11, 11-Sec.11
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	, T. <u>50</u> N. S., R. <u>8</u> E. W.	12-Sec.11, 15-Sec.11
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-15 & 2-5, 19 80, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 9-Sec.11 East 1/16 Corner of Section 11.
- 11-Sec.11 South-West 1/16 Corner of Section 11.
- 12-Sec.11 South 1/16 Corner of Section 11.
- 15-Sec.11 West 1/16 Corner on South side of Section 11.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 9-Sec.11 Placed corner 1,320' East of post at center of section.
- 11-Sec.11 Placed corner 1,319.3' North of the section line and 1,310.4' West of the N-S 1/4 line.
- 12-Sec.11 Placed corner midway bet. a wood post at center of section and the South 1/4 corner.
- 15-Sec.11 Placed corner midway and on line bet. 1/4 cor. to East and Sec. Cor. to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminum cap at all 4 corners. Bearings:

- 9-Sec.11 12" Hemlock, S70°E, 27.5' & 14" Spruce, S8°E, 35.8' & 7" S. Maple, North, 15.7'.
- 11-Sec.11 20" Hemlock, S67°W, 32.6' & 4" Hemlock, N75°E, 13.0' & 12" Spruce, S45°E, 9.9'.
- 12-Sec.11 8" Hemlock, S62°W, 43.7' & 12" Hemlock, N78°E, 43.7' & 6" Hemlock, N38°E, 24.6'.
- 15-Sec.11 12" Y. Birch, S55°W, 28.1' & 7" S. Maple, N63°W, 8.9' & 6" S. Maple, N26°E, 7.9' & 7" Spruce, S83°E, 27.7'.

SIGNED BY _____ DATE 10-9-80

Billy D. Buckler
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET