

40

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

Located in:

Corner Code #

(County)

1. Public Land Survey

T 50N R 8W 67

T 50N R 8W E13

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

E13 Aug 04 1997

G7 Nov 13 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7							●						
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13							●						

A. Description of original monument and accessories and/or subsequent restoration:

(G7) Corner common to Sections 15-16-21-22. Corner re-witnessed as found in 1994 by the undersigned: Found 1" pipe with 4" Brass cap. The 1994 accessories are as follows: 5" J. Pine N69W 4.5', 6" J. Pine N27E 2.7', 6" J. Pine S10E 7.2', 10" J. Pine N74W 85.9' (1952 NBT). Placed a squared and scribed cedar post adjacent.

(E13) Corner common to Sec. 32-33 T50N-R8W and Sec. 4-5 T49N-R8W. Corner re-monumented in 1958 by Billy D. Buckler: "Replaced as set by Marcus Schaaf, Reg. Surveyor. Maple B.T. (Green) in place bearing S20W 25 links. Tree in good condition. Corner shown to us by B. McTiver, District Forester. Corner placed and witnessed March 5, 1958". Buckler placed a 1" pipe with 4" Brass Cap and made the following witnesses: 15" Yellow Birch S23W 58 links "S5 NBT", 16" Yellow Birch S68E 56.5 links "S4 NBT".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G7) Found and accepted the monument, as described, in good condition, and at record bearing and distance from the 1952 and 1994 witnesses. Left the monument and post in place and, to facilitate GPS observations, removed the 1994 witnesses trees. Marked 4 new accessories as described below. Corner recovered and re-witnessed by D. Lampela, Newberry District Office.

(E13) Found the 1958 monument, a 1" I.D. iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the remains of the 1958 witnesses: The 15" Y. Birch is dead and down, the 16" Y. Birch is a dead stub. The original Maple B.T. is now gone, apparently cut and removed. Left the monument in place and marked 4 new witnesses as described below. Corner re-witnessed by T. Stark, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G7) Found 1" pipe with 4" Brass cap. Blazed, scribed, and set measuring nails in the following:

7" J. Pine N57W 18.9' "S16 NBT"
7" J. Pine N28W 8.85' "S16 NBT"
11" J. Pine N63E 16.35' "S15 NBT"
8" J. Pine S51E 31.15' "S22 NBT"

Bearings are magnetic.

(E13) Found 1" pipe with 4" Brass cap. Blazed, scribed, and set measuring nails in the following:

6" Maple S31E 7.7' "S4 NBT"
14" Hemlock S76W 40.0' "S5 NBT"
10" Maple N02E 38.05' "S33 NBT"
10" Maple N40W 25.25' "S32 NBT"

Bearings are magnetic.



Signed by Stephan J. Szyszkoski

Date 8/7/97

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division