

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

39

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 8W	C13
	T 50N R 8W	D13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

D13 Aug 05 1997

C13 Aug 04 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C13) Corner common to Sections 31-32, T50N-R8W and Sections 5-6 T49N-R8W. Corner monumented in 1952 by Dean C. DeLaMater as follows: "This corner was pointed out to me by B. McTiver, District Forester, of Newberry. One original B.T. still in place, poor condition. Corner was placed and witnessed May 28, 1952". DeLaMater placed a 1" pipe with 4" brass cap at the corner and marked the following: 10" J. Pine N57E 11 links, 14" R. Pine S33E 48 links.

(D13) Quarter corner common to Section 32 T50N-R8W, and Section 5 T49N-R8W. Corner established in 1850 by Wells Burt as follows: "West on South side of Section 32...35.00 Enter level wet land...40.00 Set qr. Section post Y. Pine 8 N49E 33, Y. Pine 5 N77W 17. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C13) Found the 1953 monument as described, a 1" I.D. iron pipe capped with a 4" brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the remains of the 1952 accessories: the 10" J. Pine is dead but standing, and the 14" R. Pine has been cut. The original B.T. noted above was not recovered. Left the monument in place and marked 4 new witnesses as described below. Corner recovered and re-witnessed by T. Stark, Newberry District Office.

(D13) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record between monumented section corners 2658.0' east and west. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, the original call for level wet land to the east checks. Corner placed and witnessed by T. Stark, Newberry District office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C13) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following:

14" R. Pine N60W 38.9' "S31 NBT"
 14" R. Pine N11E 28.55' "S32 NBT"
 12" W. Pine S14W 9.85' "S6 NBT"
 12" W. Pine S09E 28.65' "S5 NBT"

Bearings are magnetic.

(D13) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

14" W. Pine N18E 12.8' "1/4S NBT"
 8" Spruce N30E 17.4' "1/4S NBT"
 12" W. Pine S64E 14.7' "1/4S NBT"
 16" W. Pine S05E 20.9' "1/4S NBT"
 5" squared and scribed W. Pine N30W 32' to center. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/7/97

For the Michigan Department of Natural Resources - Forest Management Division