

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Loca

(County)

Located In:

Corner Code #

- 1. Public Land Survey
T 50N R 8W F7
T 50N R 8W F9
T R
T R
- 2. Property Controlling
in Section S 21 T 50N R 8W 10
S T R
- 3. Miscellaneous
Property in Sec S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

10 May 05, 1994
F9 May 09, 1994

I, Stephan J. Szyzko, in a field survey on F7 March 01, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (F7) Quarter corner common to Sections 16-21. Corner reestablished by single proportionate measurement to the original record in 1977 by Jerry L. Wilcox, RLS. The 1977 record states: Set 1/2" rod/cap (s.p.) N50W 10' R. Pine 14.88', N45E 4' R. Pine 11.33', S65E 14' J. Pine 6.47', S05W 14' R. Pine 14.71'. Found no subsequent record.
- (F9) Quarter corner common to Sections 21-28. Corner previously re-monumented in 1970 by Billy D. Buckler from one original bearing tree, a Y. Pine stub with faces plain. The 1970 record states: Set 1" pipe with 4" aluminum cap. Witnesses: 9" R. Pine N65W 46.3', 7" R. Pine S28 9.9'.
- (10-Sec. 21) South 1/16 corner between Sections 20-21. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (F7) Found, verified the proportionate position of, and accepted Wilcox's monument as described, set flush with the ground, at record bearing and distance from the 1977 accessories, all in good condition. Noted that the J. Pine NBT is actually a W. Pine. Found measuring nails in all 4 NBTs. Drove a 1" I.D. x 36" iron pipe capped with a yellow plastic cap stamped "MICH DNR LS 33985" over Wilcox's re-rod and placed a 4" cedar post, squared and scribed, adjacent.
- (F9) Found and accepted Buckler's monument and accessories as described. The bearing to the R. Pine NBT which is incomplete in the 1970 record was found to be S28E. The Y. Pine stub S78E 58 links, an original BT, noted on the 1970 record, is still in place. Placed measuring nails with tags in the 1970 NBTs and marked two new bearing trees as described below. The corner lies in NE corner of a J. Pine cutting, current regeneration is 3"-4" J. Pine.
- (10-Sec. 21) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between perpetuated original corners 1316.83' North and South. Monumented the corner position with a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (F7) Set a 1" capped iron pipe over the 1/2" capped reinforcing rod placed in 1977 by Jerry Wilcox, RLS. Recovered the following record NBTs:
12' N. Pine N50W 14.88'
6' R. Pine N45E 11.33'
16' W. Pine S65E 6.47'
16' R. Pine S05W 14.71'
Blazed and scribed all above "1/4S NBT"
Bearings are magnetic.
- (F9) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following new bearing trees:
10' J. Pine S28E 19.5' "1/4S NBT"
8' J. Pine N28E 12.1' "1/4S NBT"
The 1970 NBTs:
12' R. Pine N65W 46.75'
10' R. Pine S28E 10.3'
Placed a 5" cedar post, squared and scribed, adjacent. Bearings are magnetic.
- (10) Set 1" iron pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following bearing trees:
5' J. Pine N74W 16.1' "81/16 BT"
6' J. Pine N09E 26.4' "81/16 BT"
10' J. Pine N32E 19.6' "81/16 BT"
8' W. Pine S26W 35.6' "81/16 BT"
Placed a 5" cedar post, squared and scribed, adjacent. Placed a location poster on a 6" J. Pine 57' north of the corner at a trail rd. course N-SE. Bearings are magnetic.

Signed by Stephan J. Szyzko

Surveyor's Michigan License No. 33486

