

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 8W	C11
	T 50N R 8W	C12
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Aug 11 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11		●										
12	31	●	32	33	34	35	36					

A. Description of original monument and accessories and/or subsequent restoration:

- (C11) Corner common to Sections 29-30-31-32. 1971 - Reestablished by Billy D. Buckler, RLS by double proportionate measurement from corners 1/2 mile north, 1/2 mile south, 1/2 mile east and Meander Corner on west side of Culhaine Lake. Set 1" pipe with 4" aluminum cap. 22" W.Pine S61W 28.2', 8" Tamarack S10W 26.3'.
- (C12) Quarter corner common to Sections 31 and 32. 1959 - Remonumented by Billy D. Buckler RLS: Replaced cor. from two Y.Birch BTs S16W 28 links and N16E 33 links. Squared and scribed 8" R.Pine 3 links SW of corner. Set 1" pipe with 4" brass cap. 9" W.Pine N40E 29.5 links, 13" R.Pine S46E 37 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (C11) Recovered the 1971 monument in good condition and at record bearing and distance from the 1971 witness trees, both in good condition. Left the monument in place and made new witnesses as described below.
- (C12) Recovered the 1959 monument in good condition and at record bearing and distance from the two 1959 NBTs, both in good condition with overgrown blazes. Left the monument in place and made new witnesses as described below. Found 2 stumps, no markings visible, probably the original BTs noted in the 1959 record, at record bearing and distance.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (C11) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
24" W.Pine S65W 28.9' old marks *
9" Tamarack S14W 26.4' mrkd "S31" *
11" Cedar N70E 9.15' mrkd "S29 NBT"
8" twin Cedar S41E 5.85' "S32 NBT"
Bearings are magnetic. Distances are to nail with tag. * denotes 1971 NBT. | (C12) Found 1" I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in:
13" W.Pine N41E 19.9' mrkd "1/4S" *
16" R.Pine S42E 24.35' do *
13" R.Pine S75W 2.3' mrkd "1/4S NBT"
6" W.Pine N67W 9.6' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1959 NBT. |
|---|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/25/05

For the Michigan Department of Natural Resources, Office of Land and Facilities