

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 50N R 8W	MC north of E12	
	T _____ R _____	_____	
	T _____ R _____	_____	
	S _____ T _____ R _____	_____	
2. Property Controlling in Section	S 32 T 50N R 8W	14	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

14 Aug 25 2005
 MC Jun 19 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MC north of E12) Meander Corner on South shore of Bodi Lake between Sections 32 and 33. 1958 - Remonumented by Billy D. Buckler RLS: Replaced as witnessed by Marcus Schaaf, Reg. Surveyor. Found Iron pipe and wood post in place. Found no evidence of original BTs. Position fits with Meander Corner between 28/33 which is 1.08 chains North and 3.5 chains East of this corner. Set 1" pipe with 4" brass cap. 13" White Spruce S5E 96 links, 7" Balsam S38E 100 links. July 28, 1974 notes by Mr. Buckler say: Reset Meander Corner which was removed by ice. Both witnesses in excellent condition. Cor. lies in water's edge.
 (14-Sec. 32) South 1/16 corner between Sections 32 and 33. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC 32/33) Found Buckler's W.Spruce NBT and chopped out bottom blaze to reveal iron marks. Recovered Buckler's Balsam NBT dead and down. The 1958 monument was moved by persons unknown to a location that appears to be an estimation of where the Section corner would have been set in the lake. Dug at the record position and found the cement base of the Schaaf monument noted in the 1958 record, in good condition. Placed a new monument at the position of the Schaaf monument and at record bearing and distance from the 1958 witnesses. Placed a wood post adjacent. Made both the monument and post firm in concrete. Cut the aluminum cap off of the 1958 monument in the lake. 8/4/2005 - verified the 1995 witnesses, which are stated below.
 (14-Sec. 32) Established the corner midway and on line between Section corner 1309.45' south and Quarter corner 1309.45' North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC 32/33) Set 1"IDx36 I.pipe with 4" alum. MDNR cap, set in concrete. Set measuring nails in: 18" W.Spruce S05E 63.7' mrkd "MC" * 3" Cedar S34E 50.8' mrkd "MC NBT" 3" Maple S05W 77.6' do 3" Maple S21W 29.0' do Set sq'd cedar post in concrete, adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1958 NBT	(14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Balsam N58E 10.15' mrkd "S1/16 BT" 6" Maple N28E 14.3' do 8" W.Birch N54W 21.55' do 12" Hemlock S25E 15.5' do Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/25/05

For the Michigan Department of Natural Resources, Office of Land and Facilities