

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 8W	MC West of F11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T 50N R 8W	10
	S 32 T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

10 Sep 07 2005  
 MC Aug 25 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(MC West of F11) Meander Corner on the southeasterly shore of Bodi Lake between Sections 28 and 33. Remonumented in 1958 by Billy D. Buckler RLS from two White Pine B.T.s bearing S28W 65 links and N75E 96 links. Found scribe marks on stump bottoms. Mr. Buckler placed a 1" pipe with 4" brass cap at the corner position and marked: 16" White Pine N72E 191 links, 9" Red Pine S80E 88 links.  
 (10-Sec. 32) South 1/16 corner between Sections 31 and 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC between 28 and 33) The 1958 monument was not recovered. The original W.Pine accessories were not recovered. Found one of the two 1958 witness trees, W.Pine 22" diameter, with lower blaze chopped out, revealing the 1958 scribing. Found no other reliable physical evidence apart from this single NBT. Remonumented the corner at magnetic record bearing and distance from the 1958 W.Pine NBT after applying an index correction to the record bearing. The index correction was determined by averaging the differences between the observed and record magnetic bearings to a number of NBTs marked by Mr. Buckler at various corners set in his 1958 survey around Section 32.  
 (10-Sec. 32) Established the corner midway and on line between Section corner 1316.27 feet south and Quarter corner 1316.27 feet north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 22" W.Pine N74.5E 126.88' old blazes * 10" R.Pine S05E 72.06' mrkd "MC BT" 10" R.Pine S08W 38.08' do 8" R.Pine S48W 154.41' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1958 NBT.	(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 18" R.Pine S34E 14.87' mrkd "S1/16 BT" 8" W.Pine S85E 30.45' do 10" R.Pine N22W 19.1' do 14" R.Pine N80W 52.75' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	--

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 10/25/05

For the Michigan Department of Natural Resources, Office of Land and Facilities