

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 8W	A11
	T 50N R 8W	MC bet. B11-C11
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11		MC											
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 10/08/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A11) Corner common to Sections 30 and 31 T50N-R08W and Sections 25-36 T50N-R09W. 1985 - Remonumented and rewitnessed by G.W.Wiggins RLS, perpetuating the 1952 position of record, monumented by Billy D. Buckler RLS from an original BT. NBTs: 10" R.Pine S65W 22 links, 10" R.Pine N2E 28 links. Set pipe. 14" R.Pine S70W 14.52', 14" R.Pine N02E 18.48', 10" R.Pine S55E 14.2', 8" W.Pine S41W 18.2'.

(MC) Meander corner on the north line of Section 31 at the East shore of Culhane Lake. 1971 - The corner was reestablished by Billy D. Buckler RLS on the Section line between Section corner C11 and the Meander Corner on the West shore of Culhane Lake. Set 1" pipe with 4" aluminum cap. 11" Cedar N02W 8.4', 9" Cedar S09E 9.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A11) Recovered the 1985 monument, a 1" ID I.pipe with 4" alum. MDNR cap, at record bearing and distance from the 1952 witness R.Pine trees and the 1985 witness R.Pine SE. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(MC) Recovered the 1971 monument in good condition and at record bearing and distance from the 1971 NBTs, both in good condition. The GLO record distance from the MC to corner C11 is 9.45 chains (623.7'). I found the distance from the 1971 monument to C11 to be 593.64' (Mr. Buckler's record states 601') meaning, without application of any index correction, that the 1971 monument is a witness corner 30.06' east of the MC position. I observed the MC monument to be 4.4' North of a straight line between C11 and the original MC on the West Shore of Culhane Lk.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A11) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 15" R.Pine S70W 15.65' mrkd "S25" 1952 NBT  
 16" R.Pine N03E 18.54' "S30" do  
 13" R.Pine S53E 14.64' open blazes 1985 NBT  
 14" R.Pine N53W 41.48' mrkd "S25 NBT"  
 Bearings are magnetic.

(MC) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" Cedar N08E 8.75' mrkd "MC" 1971 NBT  
 9" Cedar S10E 10.03' do do  
 18" Cedar S38W 6.35' mrkd "MC NBT"  
 7" Spruce S58E 18.6' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

