

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 8W	B13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S 31 T 50N R 8W	3
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 3 10/04/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B13) Quarter corner common to Section 31 T50N-R08W and Section 6 T49N-R08W. 1952 - Remonumented in the original position by Dean C. DeLaMater RLS. Found two original B.T.s still in place, in excellent condition. Set 1/2"x24" Iron bar. 8" R.Pine S25W 56 links, 10" J.Pine S44E 46 links.

(3-Sec. 31) North 1/16 corner between Section 31 T50N-R08W and Section 36 T50N-R09W. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B13) Recovered the 1952 monument, bent over, with a 1/2" ID I.pipe adjacent, also bent. The bar was found at record bearing and distance from the 1952 NBTs, both in good condition. Removed both the bar and pipe and, at the position of record, drove a new monument.

(3-Sec. 31) Established the corner midway and on the Range line between Section corner 1317.55' north and Quarter corner 1317.55' south. From the position thus established, I found a 1/2" iron, not of record, N33W 2.85' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B13) Set 1"ID I.pipe with yellow plastic cap stamped MICH DNR LS33986. Set measuring nail with MDNR tag in the side of:
 18" R.Pine S23W 37.7' mrkd "1/4S" 1952 NBT
 16" J.Pine S43E 31.0' open blaze do
 5" J.Pine N55W 27.0' mrkd "1/4S NBT"
 7" J.Pine N27E 24.75' do
 Bearings are magnetic.

(3) Set 1"ID I.pipe with yellow plastic cap stamped "MICH DNR LS33986", buried in the east track of a N-S fire lane. Set measuring nail with MDNR tag in the side of:
 14" R.Pine N40W 19.18' mrkd "N1/16 BT"
 8" Oak N69E 14.32' do
 11" Oak N27E 29.55' do
 14" W.Pine S88W 27.6' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

