
LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For	corners	in
101	COLLICIO	

Luce	Located In:	Corner Code #									
(County)	_										
1. Public Land Survey	T R T R										
2. Property Controlling in Section	S 31 T 50N R 8W S 31 T 50N R 8W S T R	13 16									
3. Miscellaneous Property in Sec.	S T R S T R			Reg	jistei	r of C	eed	s Sta	amp	. & F	File N
4. Lot No. , Red 5. Private Claims	ecorded Plat		1 A	В	ç	D	E	F	G	н	<u> </u>
	10/04	W2007	2 -	- 6-		- [· - 5-		- 4-	+	_ å. —∔	_
Cumban I Campaloolei	in a field suprove on 10/04	1/2007 do hereby state		1	Į.	l	- [Ĺ		, ,	

lumber



that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey 5 instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of 6 a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with 7 the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, g re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Stephan J. Szyszkoski , in a field survey on

A. Description of original monument and accessories and/or subsequent restoration:

(13-Sec. 31) Southeast 1/16 corner, Section 31. Not established in the original survey.

(16-Sec. 31) East 1/16 between Section 31 T50N-R08W and Section 6 T49N-R08W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 31) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(16-Sec. 31) Established the corner midway and on the township line between Section corner 1315.52' east and Quarter corner 1315.52' west. From the position thus established, I found a 1/2" iron, not of record, S20E 2.23' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: mrkd "SE1/16 BT" 11" W.Pine S62E 17.97' 7" R.Pine S71W 30.2' do do 14" R.Pine N36E 24.1' 14" R.Pine N17W 38.31' do Bearings are magnetic.

(16) Set 1"IDx36" I.pipe with yellow plastic cap stamped MICH DNR LS33986. Set measuring nail with MDNR tag in the side of:

mrkd "E1/16 BT" 15" R.Pine N10W 6.15'

10" R.Pine SO1E 18.8' do do 4" J.Pine N81W 18.85' 14" R.Pine N77E 49.5' do

Bearings are magnetic. The center of an E-W road is 9' south.

33986 Surveyor's Michigan

Date

03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BO

LAND Sesis sed Jan., 1983

Rervised Oct., 1995

OF MICH

yszkosk LAND

URVEYOR

STEPHAN.

47034

47035