

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49-50 NR. 9 W . . .

----- Luce ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 5-6-31-32 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER	5" Jackpine	S 68° E	28 links
		"S 5 NBT"	
	5" Jackpine	S 70° W	4 1/2 links
		"S 6 NBT"	
	6" Jackpine	N 48° W	16 links
		"S 31 NBT"	

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner as perpetuated by Marcus Schaff, Reg. Surveyor.

Found 2" iron pipe buried in ground. Found two jackpine B.T.s bearing S 60° E 37 links and S 16° W 32 links down and in poor condition.

Corner lies on west edge of woods road and at end of fire lane from south.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/13/57  
REGISTERED LAND SURVEYOR