

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 50 N. R. 9 W


Luce COUNTY

DESCRIPTION OF CORNER Witness Corner to Meander Corner for Secs. 26-27. Set at 47.00
Chains from South

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/18/64 with Forestry Aide Hibick

WITNESSES TO CORNER..... 12" J. Pine (W.C. to M.C. MBT) S81°W, 23 Lns.



8" J. Pine (W.C. to M.C. MBT) N76°E, 32½ Lns.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed on Mean Bearing of Section Lines to East and West. Witness Corner Located 1.497 Chains South of point for M.C.

SURVEYOR'S SEAL

SIGNED Frank J. Gray DATE 8/18/1964
REGISTERED LAND SURVEYOR