

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 50N N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER East 1/16 corner, Sec. 25

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 1-14-70

WITNESSES TO CORNER..... 10" Red Pine (E 1/16 BT) N41°E 10.2'



CIRCLE CORNER REGISTERED

14" Red Pine (BT) S12°W 18.5'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner placed midway and on line between the East  $\frac{1}{4}$  Cor and the center of Sec. 25; according to the Rules for sub-division of standard sections.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4-14-70  
Billy D. Buckler  
REGISTERED LAND SURVEYOR