

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

#37

For corners in

LUCE <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T 50N R 9W	M9
	T _____	_____
	T _____	_____
	T _____	_____
2. Property Controlling In Section	S 25 T 50N R 9W	2
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

I, STEPHAN J. SZYSZKOSKI, in a field survey on October 31, 1991, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M9 CORNER PERPETUATED BY BILLY D. BUCKLER, R.L.S. 8887 MAY 29, 1952 FROM TWO ORIGINAL BEARING TREES. BUCKLER PLACED A 1" PIPE WITH A 4" BRASS MICHIGAN DEPT. OF CONSERVATION CAP AT CORNER WITH THE FOLLOWING ACCESSORIES: 12" RED PINE N25W 27 LINKS, 10" RED PINE S26W 19 LINKS

(2) CORNER ESTABLISHED BY BILLY D. BUCKLER, R.L.S. 8887 8/29/63 MIDWAY BETWEEN SECTION CORNER TO EAST AND 1/4 CORNER TO WEST, AND MONUMENTED WITH A 1" PIPE WITH A 4" ALUMINUM CAP. BUCKLER'S ACCESSORIES: 10" RED PINE N40E 35.5 LINKS, 10" RED PINE S19E 40 LINKS, 11" RED PINE S46W 17.5 LINKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M9 FOUND AND ACCEPTED 1" PIPE WITH 4" BRASS MICHIGAN DEPT. OF CONSERVATION CAP IN ACCORD WITH ABOVE ACCESSORIES. BASE BLAZES ARE NEARLY OVERGROWN.

(2) FOUND AND ACCEPTED A 1" PIPE WITH A 4" ALUMINUM MICHIGAN DEPT. OF CONSERVATION CAP. BEARING TREES CHECK AS FOLLOWS: SE IS GONE, NE CHECKS TO A RED PINE STUMP, THIRD BT FROM ABOVE WAS FOUND WITH BASE SCRIBED AND AT RECORD DISTANCE BUT BEARING N46W NOT S46W. DISTANCE EAST TO M9 MEASURES 1317.87' COMPARED TO BUCKLER'S 1317.2'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M9 1" PIPE WITH 4" BRASS CAP: 1. S15E 38.65' SET NAIL AND MICHIGAN DEPT. OF NATURAL RESOURCES TAG IN E. FACE 16" R. PINE; 2. S87W 7.17' SET NAIL AND MDNR TAG IN NORTH FACE 7" R. PINE; 3. S26W 12.67' SET NAIL AND MDNR TAG IN WEST FACE 18" R. PINE; 4. N25W 18.28' SET NAIL AND MDNR TAG IN EAST FACE 17" R. PINE WITH OLD BASE BLAZE. (1&2 ABOVE SCRIBED AT BH AND BASE, 3 AT BH)



(2) FOUND 1" PIPE WITH 4" ALUMINUM CAP:  
1. S43E 7.60' SET NAIL AND MDNR TAG IN W. FACE 12" R. PINE; 2. S06E 10.92' SET NAIL AND MDNR TAG IN W. FACE 10" R. PINE;  
3. S32W 17.61' SET NAIL AND MDNR TAG IN N. FACE 10" R. PINE; 4. N46W 11.65' SET NAIL AND MDNR TAG IN E. FACE 12" R. PINE.  
(1, 2, AND 3 ABOVE SCRIBED 1/16 AND BT, 4 SCRIBED 1/16).

Signed by

*Stephan J. Szyszkoski*

Date

11-4-91

Surveyor's Michigan License No.

33986