

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 9W	M10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 01/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M10) Quarter corner common to Section 25 T50N-R09W and Section 30 T50N-R08W. 1970 - Reestablished by Billy D. Buckler RLS midway and on line between adjacent section corners. Set 1"ID I.pipe with 4" aluminum cap. 22" W.Pine S85E 12.0', 10" R.Pine N22W 8.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M10) Found the 1970 monument in good condition and at record bearing and distance from the 1970 witness trees, both in good condition. The monument marks a position S32W 5.3', as I measure it, from the midway position described in the 1970 record. I accept the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M10) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 22" W.Pine S81E 12.8' open blazes 1970 NBT
 12" R.Pine N18W 9.2' mrkd "1/4S" do
 26" W.Pine S36W 10.8' mrkd "1/4S NBT"
 8" R.Pine S24E 9.95' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities