

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 9W	K11
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 25 T 50N R 9W	3
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 3 01/16/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K11) Section corner common to 25-26-35-36. 1952 - Remonumented by Dean C. DeLaMater RLS in the original position as determined from one original B.T., still in place, in poor condition. Set 1" pipe with 4" brass cap. 20" W.Pine S70W 58 links, 10" J.Pine N53E 21 links.

(3-Sec. 25) North 1/16 corner between Sections 25 and 26. 1964 - Established by F.J.Bray RLS midway and on line between Section corner to north and 1/4 corner to south. Set 1" I.pipe with 4" alum. cap. 5" R.Pine S89E 45 links, 12" J.Pine West 06 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K11) Found the 1952 monument in good condition and at record bearing and distance from the 1952 witnesses. The W.Pine SW (this tree is actually a Red Pine) is in good condition with overgrown blazes. The J.Pine NE is a stump. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. The original BT noted in the 1952 record was not recovered.

(3-Sec. 25) The 1964 monument was not recovered. Remonumented the corner in the 1964 position, in the hole apparently left after the monument's extraction by persons unknown, which hole was found at record bearing and distance from the BT Red Pine SE, found in good condition. The J. Pine BT, West, was not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K11) Fd. 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 23" R.Pine S72W 38.9' mrkd "S35" 1952 NBT
 6" W.Pine N62W 6.13' mrkd "S26 NBT"
 10" W.Pine N58E 4.47' "S25 NBT"
 7" W.Pine N12E 10.45' "S25 NBT"
 Bearings are magnetic.

(3) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 15" R.Pine S80E 30.24' mrkd "N1/16" 1964 BT
 6" J.Pine S25W 6.45' mrkd "N1/16 BT"
 4" J.Pine N11W 5.76' do
 5" J.Pine N63E 3.1' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

