

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 9W	L11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 25 T 50N R 9W	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on L11 01/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L11) Quarter corner common to Sections 25 and 36. 1970 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" pipe with 4" alum. cap. 15" R.Pine N20W 3.0', 8" W.Pine S80W 14.7'.

(8-Sec. 25) West 1/16 corner, Section 25. 1970 - Established by Billy D. Buckler RLS, midway and on line between Center of Section and West 1/4 corner. Set 1" pipe with 4" alum. cap. 12" J.Pine N58W 15.7', 8" J.Pine N26E 13.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L11) Found the 1970 monument, in good condition and at record bearing and distance from the 1970 witness trees, both in good condition. I found the monument to be west of the intended proportionate position by 17'. I note that Mr. Buckler had previously subdivided this section and monumented many of the interior corners. Those corners have been in place and accepted for over 35 years. I did not desire to disturb the monumentation of this section by adjusting the monument to the exact proportionate position intended in 1970 and so accepted the monument as marking the position for the 1/4 corner.

(8-Sec. 25) Found the 1970 monument in good condition, at the record position, and at record bearing and distance from the two 1970 witnesses. The J.Pine NW is standing dead. The J.Pine NE is in good condition. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L11) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 16" R.Pine N30W 3.5' mrkd "1/4S" 1970 NBT
 12" W.Pine S83W 15.8' do do
 10" W.Pine N39E 20.95' mrkd "1/4S NBT"
 8" R.Pine S54E 2.3' do do
 Bearings are magnetic.

(8) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 10" J.Pine N28E 13.69' mrkd "W1/16" 1970 BT
 6" J.Pine N70W 21.88' mrkd "W1/16 BT"
 6" J.Pine S45W 28.32' do do
 6" J.Pine S21E 14.8' do do
 Bearings are magnetic.

Signed by

Stephan J. Szyszkoski

Date

03/18/2008

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

