

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 9W	K9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 25 T 50N R 9W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 01/16/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(K9) Corner common to Sectitons 23-24-25-26. 1963 - Remonumented by Billy D. Buckler RLS at the position of a found 4" concrete-filled iron pipe, placed and witnessed by an unknown surveyor. Set 1" pipe with 4" aluminum cap. 12" J.Pine S18W 44 links, 12" J.Pine South 90 links. Corner lies on top of escarpment.

(13-Sec. 25) Southeast 1/16 corner, Section 25. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K9) Found the 1963 monument in good condition but did not accept its position as the corner position. It has clearly been moved from the record position by persons unknown and had been reinstalled S68W 41' from the position of record. The 1963 position of record was reestablished from the 1963 NBTs, the J.Pine SW is standing dead, the J.Pine South is a stump. The 1963 position was confirmed by measurements made to existing monuments to the east and south, along the north and west lines of Section 25. Remonumented the 1963 position and removed the monument which was found marking the erroneous position.

(13-Sec. 25) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K9) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 7" J.Pine S35W 21.6' mrkd "S26 NBT"  
 10" J.Pine S76W 37.18' do  
 6" R.Pine S20E 26.55' "S25 NBT"  
 5" J.Pine N72E 1.87' "S24 NBT"  
 Bearings are magnetic. Corner falls on the top of bluff.

(13) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" W.Pine S46W 15.7' mrkd "SE1/16 BT"  
 5" J.Pine S06W 24.97' do  
 5" J.Pine S54E 6.05' do  
 6" J.Pine N74E 12.7' do  
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*  
 Surveyor's Michigan License No. 33986

Date 03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

