

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 9W	K10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 25 T 50N R 9W	4
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on K10 01/15/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K10) Quarter corner common to Sections 25 and 26. 1964 - Remonumented by F.J.Bray RLS at the position of an old wood post set in Iron Pipe encased in concrete block. Set 1" I.pipe with 4" alum. cap. 12" J.Pine S50E 24 links, 12" J.Pine N77W 36 links.

(4-Sec. 25) Northwest 1/16 corner, Section 25. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K10) Found the 1964 monument in good condition and at record bearing and distance from the 1964 NBT J.Pine NW, now a stump. The J.Pine SE NBT was not found. The concrete-encased pipe was placed, I suspect, in the 1920s by Marcus Schaaf RLS of the Michigan Dept. of Conservation. An iron pipe encased in a concrete block at its base was a "signature" monument of Mr. Schaaf in northern Luce Co. Did not excavate in search of the Schaaf monument, due to frozen ground. I accepted the 1964 monument as the best available evidence of the position of the original corner.

(4-Sec. 25) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K10) Found 1"ID I.pipe with 4" MI Dept. of Conservation cap. Set meas. nail with MDNR tag in the side of:
 5" J.Pine N48E 1.92' mrkd "1/4S NBT"
 7" J.Pine S72W 10.62' do
 8" J.Pine S27W 18.87' do
 5" J.Pine S70E 19.92' do
 Bearings are magnetic.

(4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 22" R.Pine S30W 16.93' mrkd "NW1/16 BT"
 5" J.Pine N34W 17.75' do
 7" J.Pine N45E 23.45' do
 10" R.Pine S56E 82.6' do
 Bearings are magnetic.

Signed by

Stephan J. Szyszkoski

Date

03/18/2008

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

