

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T 50N R 9W	L10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 25 T 50N R 9W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on 01/15/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(L10) Center of Section 25. 1970 - Established by Billy D. Buckler RLS at the intersection of 1/4 lines. Set 1" pipe with 4" aluminum cap. 10" Red Pine N60E 4.9', 10" W.Pine S31W 5.5'.

(5-Sec. 25) North 1/16 corner, Section 25. Not established in the original survey. 1970 - Corner established by Billy D. Buckler RLS midway and on line between Center of Section and North 1/4 corner. Set 1" pipe with 4" alum. cap. 7" Red Pine N30W 1.7', 8" Jack Pine S14W 4.7'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L10) Found the 1970 monument in good condition, at the record position, and at record bearing and distance from the 1970 witness trees, both in good condition. Accepted the monument as a careful and faithful establishment of the position of the corner.

(5-Sec. 25) Found the 1970 monument in good condition, at the record position, and at record bearing and distance from the 1970 witnesses, the species of which were transposed on the 1970 record. The 7" J.Pine NW is now a stump. The 8" R.Pine SW is in good condition.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L10) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 14" R.Pine N64E 5.35' mrkd "CS" 1970 BT  
 15" W.Pine S33W 5.61' do do  
 6" W.Pine N16W 5.07' mrkd "CS BT"  
 7" R.Pine S80E 19.85' do  
 Bearings are magnetic.

(5) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" R.Pine S16W 4.7' mrkd "S1/16" 1970 BT  
 11" R.Pine S78E 4.06' mrkd "S1/16 BT"  
 8" R.Pine N02E 13.77' do  
 7" R.Pine West 25.3' do  
 Bearings are magnetic.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 03/18/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities