

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970
 Luce Co. 2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> ^{N.} / _{S.} , R. <u>12</u> ^{X.} / _{W.}	<u>C-12, C-12A</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} / _{S.} , R. _____ ^{E.} / _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-26, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners set by Francis Colman, D.S. in 1851.
C-12 Quarter Corner bet. Sec's. 31-32. Bearings were: Spruce Pine 6", N52°E, 29 lks. & Spruce Pine 5", S51°W, 4 lks.
C-12A Witness to Meander Corner bet. Sec's. 31-32. Bearings to Meander Corner were: Spruce Pine 5", S30°E, 28 lks. and Spruce Pine 8", S31°W, 11 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-12 Re-established corner on a line of North-South blazes and record distance (2640.0') North of Section Corner. Area has been clear cut and then scarified destroying any possible evidence.
C-12A Set corner on line extended thru $\frac{1}{4}$ Corner from South, at distance 966.2' North of $\frac{1}{4}$ Corner. Record = 1,133.2'. Erosion has moved bluff 150' inland.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at both corners.
C-12 New Bearings: 6" J. Pine, S80°E, 61.7' & No others near.
C-12A New Bearings: 8" J. Pine, S35°E, 35.3' and 8" J. Pine, S41°W, 55.6' Corner is 20' South of top of bluff,

SIGNED BY Billy D. Buckler
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 2-15-77



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____