

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

9-
FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>3E</u>	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1996 NOV 14 P 1:20

HANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843

L.S.C. #583m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11	●											
12	31		32		33		34		35		36	
13												

UNADILLA

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
 Black Oak 8", South 21 degrees West, 22 links
 White Oak 18", North 58 degrees East, 65 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" pointed bar at fence intersection

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11, T1N, R3E, UNADILLA, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
 097 DEG. 12.85' SET NAIL/TAG N/S 38" OAK.
 157 DEG. 14.76' SET NAIL/TAG W/S 36" OAK.
 200 DEG. 25.91' SET NAIL/TAG E/S 6" CHERRY.
 266 DEG. 40.93' SET NAIL/TAG S/S 14" OAK.

Signed by Darrell Hughes
 Surveyor's Michigan License No. 19834

Date November 11, 1996

UNADILLA TOWNSHIP, T1N, R3E

B-11, SOUTH 1/4 CORNER SEC. 30 AND NORTH 1/4 COR. SEC. 31.

FIELD: 9-30-1996 DARRELL D. HUGHES AND ASSOCIATES.

In 1995, Don Ross did an extensive survey of the SW 1/4 of Section 30, Unadilla. He found a 1-1/2" iron bar at the intersection of fencing E,W and South, per G. Fauser survey dated 11/92. Earlier in 1982, Charlie Garlock, called for "W.post" with wires E,W and South. Ross and Garlock measures to A-11 agree within 0.20'. I recommend, to the peer group, the acceptance of the iron bar for the location of B-11.

1825 Sylvester Sibley, U.S. Deputy Surveyor, "West between 30 and 31, 40.00 chains, set 1/4 section post". P.7

1982 Charlie Garlock surveys in NW 1/4 of Section 31, calls for fence post at this corner. P.8

1996 Witness list. P.10