

**SURVEY &
REMONUMENTATION**

FEB 25 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in **SECTION**

LIVINGSTON Located in: Corner Code #
(County)

1. Public Land Survey T 1N R 3E C7
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

9 / 1998 AUG 20 P 4: 42

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #864m
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CHARLES E GARLOCK, in a field survey on AUG 10, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY
GLO WITNESSES: W034-S86W-164 LKS
W012-S69E-131 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" I. ROD 3' NORTH OF ROAD CENTERLINE.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C7: NW COR. SEC. 20 T1N-R3E, UNADILLA TWP. LIV. CO. MI, REPLACED 1/2" I. ROD WITH MON BOX AND 1 1/4" X 36" BREAKAWAY I. PIPE WITH LIV. CO. REMON BRASS CAP ON TOP.
NORTH-35.57'-SP & TAG E/S 8" OAK
N10E-102.93'- SW COR. OF HOUSE ON BRICK
N40E-148.00'-SE COR. GARAGE ON BRICK
N60W-61.31'-CTR. 2 1/2" ELM
SOUTH-3.0'-CTR ROAD.

Signed by Charles E Garlock
Surveyor's Michigan License No. 14762

Date AUGUST 11, 1998

PA. 345 1970, APPROVED BY LIVINGSTON COUNTY
FEER GROUP ON 7/1/98 CO. REP VED