

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

9-  
FILED

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

- |                                       |              |              |             |
|---------------------------------------|--------------|--------------|-------------|
| 1. Public Land Survey                 | T <u>1</u> N | R <u>3</u> E | C- <u>9</u> |
|                                       | T            | R            |             |
|                                       | T            | R            |             |
|                                       | T            | R            |             |
| 2. Property Controlling<br>in Section | S            | T            | R           |
|                                       | S            | T            | R           |
| 3. Miscellaneous<br>Property in Sec.  | S            | T            | R           |
|                                       | S            | T            | R           |

1996 NOV 14 P 1:20

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48943

L.S.C. #584m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DARRELL HUGHES, in a field survey on 11-11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9			●										
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

UNADILLA

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825  
Black Oak 6", South 88-1/2 degrees West, 20 links  
White Oak 16", North 55 degrees East, 47 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron pipe in road box

\*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9, T1N, R3E, UNADILLA, replaced existing corner in existing road box with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.  
010 DEG. 28.77' SET NAIL/TAG E/S 24" HICKORY.  
255 DEG. 60.72' SET NAIL/TAG NE/S 18" ASH.  
182 DEG. 72.56' SET NAIL/TAG W/S UTILITY POLE.  
084 DEG. 135.88' SET NAIL/TAG S/S 24" ASH.

Signed by Darrell Hughes  
Surveyor's Michigan License No. 19834

Date November 11, 1996

LINADILLA TOWNSHIP, T1N, R3E

C-9, CORNER COMMON TO SECTIONS 19, 20, 29 AND 30.

FIELD: 7-9-1996 DARRELL D. HUGHES AND ASSOCIATES

Found 3/4" pipe with threaded cap in road box in centerline of Morton Road (M-106), 0.3' below asphalt grade. The Hickory and Ash trees remain, no nails found from Smith Act 74, Oak has been removed. Distances check to centerline trees. Tree and fence row to North. I recommend, to the peer group, the acceptance of this pipe for the location of C-9. Good for GPS.

1825 Sylvester Sibley, U.S. Deputy Surveyor, "North between 29 and 39, 80.00 chains, set post", P.7

1972 Clifford Smith files Act 74 for MDOT. P.8

1979 Charles Wilson uses corner in survey. P.9

1996 Witness list. P.10