

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED 9-

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

1996 NOV 14 P 1:20

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

L.S.C. #586m

Register of Deeds Stamp & File Number

- |                                    |  |             |
|------------------------------------|--|-------------|
| 1. Public Land Survey              | T <u>1</u> N R <u>3E</u>               | <u>D-11</u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
| 2. Property Controlling in Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
| 3. Miscellaneous Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DARRELL HUGHES, in a field survey on 11-11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11				●									
12		31		32		33		34		35		36	
13													

UNADILLA

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825  
White Oak 20", North 81 degrees West, 14 links  
White Oak 16", North 47-1/2 degrees East, 64 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod in centerline gravel road.

\*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11, T1N, R3E, UNADILLA, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.  
215 DEG. 63.84' SET NAIL/TAG SE/S 9" OAK.  
092 DEG. 36.58' SET NAIL/TAG N/S 44" WILLOW.  
348 DEG. 92.13' SET NAIL/TAG E/S 35" OAK.  
272 DEG. 99.12' SET NAIL/TAG N/S 26" OAK.  
125 DEG. 25'+/- DNR SIGN "PUBLIC HUNTING AREA".

Signed by Darrell Hughes  
Surveyor's Michigan License No. 19834

Date November 11, 1996

UNADILLA TOWNSHIP, T1N, R3E

D-11, SOUTH 1/4 COR. SEC. 29 AND NORTH 1/4 COR. SEC. 32.

FIELD: 9-30-1996 DARRELL D. HUGHES AND ASSOCIATES

FOUND 1/2" IRON REROD, 0.5' BELOW GRAVEL ROAD GRADE AT CENTERLINE WORDEN ROAD. TOP OF ROD PAINTED YELLOW. OLDER WITNESSES CHECK. CORNER FALLS IN LOW AREA WITH SWAMPS EAST AND WEST. NO EVIDENT OCCUPATION EAST AND WEST. GOOD FOR GPS. I RECOMMEND, TO THE PEER GROUP, THE ACCEPTANCE OF THIS REROD, SET BY GARLOCK IN 1976 "REPLACING SPIKE FOUND", FOR THE LOCATION OF D-11.

1825 Sylvester Sibley, U.S. Deputy Surveyor, "West correcting between 29 and 32, 39.54 chains, set 1/4 sec. post". P.7

1975 Charlie Garlock performs survey in SW 1/4 Sec. 29. P.8

1976 Charlie Garlock files Act 74 for above survey. "Found spike and reset with 1/2" rod." P.9

1993 Jack Smith surveys SE 1/4 of Section 29, uses this 1/2" rod, witness' same.. P.10

1996 Witness list. P.11