

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 1 N R 3 E E-5
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

1999 NOV 22 A 10:07
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI.
 48843
 TSC #1067m
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5					●								
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

UNADILLA TWP.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
 BLACK OAK 32" S43W 99 LINKS
 WHITE OAK 12" N55E 89 LINKS

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER NOT FOUND, RESET BY DOUBLE PROPORTIONATE MEASURES.
 CORNER WILL FALL IN CENTER LINE E/W ABANDONED ROAD BED.
 OCCUPATION TO SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5, T1N, R3E, UNADILLA, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk.
 Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 27 DEGREES 199.55' SET NAIL/TAG N/S 4" ELM CLUSTER.
- 21 DEGREES 37.56' SET NAIL/TAG NW/S 8" ELM CLUSTER.
- 14 DEGREES 40.27' SET NAIL/TAG E/S 8" ELM CLUSTER.
- 11 DEGREES 133.06' SET NAIL/TAG E/S 8" ELM CLUSTER.

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
 PEER GROUP ON 9-15-99, CO. REP JED

Signed by *Darrell D. Hughes*
 Surveyor's Michigan License No. 19834

Date NOVEMBER 3, 1999