

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corner in SECTION

FILED

LIVINGSTON Located in: Corner Code #
(County)

1. Public Land Survey T 1 N R 3 E E-6
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

1999 NOV 22 A 10:07

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC #1068m
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17	●	16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
WHITE OAK 22" S01W 254 LINKS
WHITE OAK 24" S41W 138 LINKS

UNADILLA TWP.

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CENTER LINE 8" DIAMETER WOOD FENCE CORNER POST. WIRE NORTH, EAST AND WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6, T1N, R3E, UNADILLA, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk.
Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

005 DEGREES 9.60' SET NAIL/TAG TOP CENTER FENCE POST.
218 DEGREES 49.53' SET NAIL/TAG NW/S 16" OAK.
184 DEGREES 97.38' SET NAIL/TAG E/S 12" CHERRY.
279 DEGREES 101.53' SET NAIL/TAG S/S 36" CHERRY.

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 9-15-99 CO. REP JED

Signed by Darrell D. Hughes

Date NOVEMBER 3, 1999

Surveyor's Michigan License No. 19834