

SURVEY & REMONUMENTATION

FEB 25 1999

FILED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

LIVINGSTON
(County)

Located in:

Corner Code #

1. Public Land Survey

T 1N R3E E10
T R _____
T R _____
T R _____

2. Property Controlling in Section

S T R _____
S T R _____
S T R _____
S T R _____

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1998 AUG 20 P 4:44

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. 866m

Register of Deeds Stamp & File Number

CHARLES E GARLOCK, in a field survey on AUG 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY
GLO WITNESSES: W018-S73E-75 LKS
W026-N85W-17 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 3/4" X 25" STEEL PIN, EARLIER THOUGHT TO BE A R.R. SPIKE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E10: E 1/4 COR. SEC. 29, T1N-R3E, UNADILLA TWP. LIV. CO. MI., REPLACED 3/4" PIN WITH MON. BOX AND 1 1/4" X 36" BREAKAWAY TOP LIV. CO. REMON PIPE WITH BRASS CAP ON TOP.
N15W-52.62'-SP & TAG W/S 14" MAPLE
N55W-56.21'-SP & TAG S/S 12" MAPLE
S65W-77.25'-CTR. 2' STEEL POST W/7' CYCLONE FENCE ATTACHED.
S75E-159.95'-SP & TAG N/S 20" OAK
SOUTH -1.0'-CTR. HWY. M-106

Signed by Charles E. Garlock
Surveyor's Michigan License No. 14762

Date AUGUST 11, 1998

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 7/1/98, CO. REP JED