

FILED 9.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1996 NOV 14 P 1:21

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#587m

Register of Deeds Stamp & File Number

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1N R 3E E-12
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DARRELL HUGHES, in a field survey on 11-11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

UNADILLA

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
Black Oak 7", North 70 degrees East, 119 links
White Oak 10", South 41 degrees East, 188 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" iron rod at downed fence intersection

*Additional descriptions and historical information on back of this sheet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12, T1N, R3E, UNADILLA, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful perpetuation of the position of the original corner.
085 DEG. 1.40' SET NAIL/TAG SE/S 6" TREE.
176 DEG. 19.25' SET NAIL/TAG W/S 8" ELM.
158 DEG. 66.28' SET NAIL/TAG W/S 10" ELM.
090 DEG. 20.18' SET NAIL/TAG S/S 8" BIRCH.

Signed by Darrell Hughes
Surveyor's Michigan License No. 19834

Date November 11, 1996

UNADILLA TOWNSHIP, T1N, R3E

E-12, EAST 1/4 COR. SEC. 32 AND WEST 1/4 COR. SEC. 33

FIELD: 10-09-1996 DARRELL D. HUGHES AND ASSOCIATES

Found 1-1/2" iron rod at downed fence intersection 6 feet East of N/S creek. Boss witness trees found, distances check, however, no nails found. I recommend, to the peer group, the acceptance of this rod for the location of E-12.

1825 Sylvester Sibley, U.S. Deputy Surveyor, "North between 32 and 33, 40.00 chains, set 1/4 post". P.7

1837 Amos Adams, county surveyor, surveys in NW 1/4 Sec. 33. P.8

1985 Gary Boss, surveys in SW 1/4 of Sec. 33. P. 9

1996 Witness list. P. 10