

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in SECTION

LIVINGSTON  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 1 N R 3 E      F-5
- T    R
- T    R
- T    R
- 2. Property Controlling    S    T    R
- in Section               S    T    R
- 3. Miscellaneous           S    T    R
- Property in Sec.         S    T    R

1999 NOV 22 A 10:07

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

ISC #1069m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

UNADILLA TWP.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO: 1825 Sylvester Sibley, Deputy Surveyor
- BLACK OAK 13" S36-1/2W 40 LINKS
- BLACK OAK 20" N44W 74 LINKS

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN CENTER LINE SPEARS ROAD, 0.6' BELOW GRAVEL GRADE. OCCUPATION TO NORTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5, T1N, R3E, UNADILLA, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 043 DEGREES 22.87' SET NAIL/TAG SE/S 16" HICKORY.
- 063 DEGREES 44.46' SET NAIL/TAG SE/S 28" OAK.
- 085 DEGREES 101.53' SET NAIL/TAG S/S TWIN 18" OAK.
- 068 DEGREES 49.80' SET NAIL/TAG SE/S 20" OAK.

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 9-15-99 CO. REP JED

Signed by Darrell Hughes

Surveyor's Michigan License No. 19834

Date NOVEMBER 3, 1999