

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

LIVINGSTON  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 1 N R 3 E      F-9
- T    R
- T    R
- T    R
- 2. Property Controlling    S    T    R
- in Section                S    T    R
- 3. Miscellaneous            S    T    R
- Property in Sec.         S    T    R

α

FILED

1999 NOV 22 A 10:07

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC# 1071m

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, DARRYL D. HUGHES, in a field survey on NOVEMBER 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

UNADILLA TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor  
A BLACK OAK 11" STANDS FOR 1/4 SECTION CORNER.

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PIPE AT DOWNED FENCE INTERSECTION, AT GRADE.  
FENCES WEST, NORTH AND EAST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9, T1N, R3E, UNADILLA, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk.  
Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 359 DEGREES 12.98' SET NAIL/TAG E/S TWIN 20" CHERRY.
- 273 DEGREES 38.42' SET NAIL/TAG S/S TWIN 24" ASH.
- 084 DEGREES 9.49' SET NAIL/TAG S/S 12" ASH.
- 129 DEGREES 132.67' SET NAIL/TAG SW/S TRIPLE 10" ASH.

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 9-15-99 CO. REP JED

Signed by Darryl D. Hughes

Date NOVEMBER 3, 1999

Surveyor's Michigan License No. 19834