

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in SECTION

LIVINGSTON
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 N R 3 E G-6
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

α'

1999 NOV 22 A 10:07

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC# 1073m

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16	●	15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

UNADILLA TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
WHITE OAK 12" S65W 54 LINKS
WHITE OAK 10" S42-1/2E 62 LINKS

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD, 2.5' WEST OF CENTER LINE GREGORY ROAD PAVEMENT AT ASPHALT GRADE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6, T1N, R3E, UNADILLA, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" in road box and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 104 DEGREES 129.60' NW CORNER HOUSE #16501.
- 226 DEGREES 35.97' SET NAIL/TAG SE/S 6" TWIN HICKORY.
- 068 DEGREES 31.15' SET NAIL/TAG N/S UTILITY POLE.
- 124 DEGREES 84.84' SET NAIL/TAG S/S 10" TWIN BIRCH.
- 353 DEGREES 182.18' SET NAIL/TAG W/S TWIN 8"-12" OAK.

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 5-5-99 CO. REP JED

Signed by Darrell Hughes

Date NOVEMBER 3, 1999

Surveyor's Michigan License No. 19834