

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1</u> N <u>R</u> 3 E	<u>G-7</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

1999 NOV 22 A 10:07

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC# 1074m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

UNADILLA TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor  
WHITE OAK 13" N26E 57 LINKS  
WHITE OAK 12" S37W 57 LINKS

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON ROD, 0.4' BELOW ASPHALT GRADE AT CENTER LINE DEXTER TRAIL TO WEST, 1.5' WEST OF CENTER LINE GREGORY ROAD PAVEMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7, T1N, R3E, UNADILLA, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" in road box and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 166 DEGREES 90.54' SET NAIL/TAG W/S 12" HICKORY.
- 104 DEGREES 30.64' SET NAIL/TAG N/S 18" TREE.
- 018 DEGREES 94.53' SET NAIL/TAG E/S TWIN 8"-12" OAK.
- 313 DEGREES 52.01' SET NAIL/TAG NE/S 26" PINE.

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 5-5-99, CO. REP JED

Signed by Darrell Hughes  
Surveyor's Michigan License No. 19834

Date NOVEMBER 3, 1999