

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 1 N R 3 E      G-8  
    T    R  
    T    R  
    T    R
- 2. Property Controlling    S    T    R  
    in Section                S    T    R
- 3. Miscellaneous            S    T    R  
    Property in Sec.         S    T    R

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor  
BLACK OAK 20" S18W 25 LINKS  
BLACK OAK 17" N32W 27 LINKS

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD 1.5' WEST OF CENTER LINE GREGORY ROAD (ASPHALT)  
20' NORTH OF CENTER LINE ABANDONED E/W RAILROAD TRACKS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8, T1N, R3E, UNADILLA, set corner with 3/4" x 36" iron pipe, affixed with 2" dia. Brass disk.  
Disk stamped "Livingston Co. Monumentation Corner, 19834" in road box and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 083 DEGREES 36.28' SET NAIL/TAG N/S UTILITY POLE.
- 309 DEGREES 29.27' SET NAIL/TAG N/S UTILITY POLE.
- 053 DEGREES 143.29' SW CORNER BANK BUILDING.
- 202 DEGREES 74.64' SET NAIL/TAG SE/S UTILITY POLE.
- 017 DEGREES 122.36' SET NAIL/TAG W/S UTILITY POLE.

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 5-5-99 CO. REP JED

Signed by Darrell Hughes  
Surveyor's Michigan License No. 19834

Date NOVEMBER 3, 1999

FILED

1999 NOV 22 A 10:07  
NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC# 1075m  
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21	●	22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

UNADILLA TWP.