

SURVEY & REMONUMENTATION

FILED

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 16 2 00 PM '94

For corners in **COMMISSION**

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

LIVINGSTON
(County)

Located In:

Corner Code ##

1. Public Land Survey	T <u>1N</u> R <u>3E</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

L.S.C. #335m
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

DARRELL HUGHES, in a field survey on NOVEMBER 4, 1994,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

UNADILLA TWP.

Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
Black Oak 7" South 77 degrees East 45 links
White Oak 16" South 51 degrees West 69 links

*Additional historical information on back of sheet

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" iron rod at fence intersection

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11, T1N, R3E, UNADILLA, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.
257 DEG. 14.97' SET NAIL/TAG N/S 18" CHERRY.
088 DEG. 6.14' SET NAIL/TAG W/S 10" RED OAK.
104 DEG. 24.33' SET NAIL/TAG N/S TRIPLE 8" RED OAK.
030 DET. 58.81' SET NAIL/TAG SE/S 20" WHITE OAK.



Signed by Darrell Hughes Date November 8, 1994
Surveyor's Michigan License No. 19834

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 17 Aug 94, CO. REP Darrell Hughes

G-11, CORNER COMMON TO SECTIONS 27, 28, 33 & 34, T1N, R3E, UNADILLA TWP.

FOUND 1/2" SMOOTH IRON ROD AT FENCE INTERSECTION E, W, AND NORTH.
WITNESS' CHECK OLDER MEASURES.

1825 Sylvester Sibley, Deputy U.S. Surveyor, set post at 80 chains from south. 40.58 chains to East. 40.60 chains to West. 40 chains to North. P.7

1837 Amos Adams, County Surveyor, surveys in NE1/4 ? Sec. 33, no information to shed light on corner location. P.8

1988 Wilson/Eckfeld find corner at fence intersection and witness. Measure 2631.48' to H-11 east. 5308.16' to I-11 east. 5356.56' GLO. P.10-12.

Poor location for GPS. In wooded area.