

SURVEY & REMONUMENTATION

FILED

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 16 2 00 PM '94

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

for corners **COMMISSION**

| | | |
|---------------------------------|-------------------------|---------------|
| <u>LIVINGSTON</u> (County) | Located In: | Corner Code # |
| Public Land Survey | T <u>1N</u> R <u>3E</u> | <u>H-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

L.S.C. #338m

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

UNADILLA TWP.

DARRELL HUGHES, in a field survey on NOVEMBER 4, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
White Oak 30" South 72 degrees East 4 links
White Oak 24" North 87 degrees West 84 links


*Additional historical information on back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. nail in top of 6" diameter wood fence corner post

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11, T1N, R3E, UNADILLA, replaced existing corner with with 2" dia. brass disk, placed atop wood fence post. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.
325 DEG. 8.82' SET NAIL/TAG SW/S 12" WHITE OAK.
285 DEG. 13.43' SET NAIL/TAG N/S 10" CHERRY.
198 DEG. 23.33' SET NAIL/TAG W/S 36" RED OAK.
164 DEG. 124.75' SET NAIL/TAG W/S UTILITY POLE.



Signed by Darrell Hughes

Date 11-8-94

Surveyor's Michigan License No. 19834

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 17 Nov 94 CO. REP [Signature]

H-11, NORTH 1/4 CORNER 34, T1N, R3E, UNADILLA TWP.

FOUND NAIL IN TOP OF 6" DIA. CEDAR FENCE POST, WIRE TO NORTH AND EAST.
OLDER WITNESS' CHECK.

1825 Sylvester Sibley, Deputy U.S. Surveyor, set 1/4 section post at
40.58 chains (2678.28') P.7.

1971 and 1973 Munsell and Garlock surveys, no witness' P.8-9.

1973 Oscar Boss finds spike in top of 6" cedar post. P.10, files Act 74,
P.11

1979 Austin Williams, in a sketch, copys Boss witness'. P.12

1987 Boss survey uses corner, no witness' 2676.68' measures to I-11,
east. (GLO 2678.88') P.13

1988 Eckfeld/Wilson uses corner in survey, measures witness' of Boss and
sets new tie. P.14-15

Not a good location for GPS.