

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 1N R 3E      I-13  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

DEC 22 10 13 AM '93  
NANCY HAVILLAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

FILED

L.S.C.# 81m  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Darrell D. Hughes a field survey on December 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 GLO: 1825  
 Black oak 12" N64E 113 lks.  
 White oak 14" N48W 355 lks.

SURVEY &  
REMONUMENTATION  
1993  
COMMISSION

Additional historical information on back of sheet:

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Fd. 3/4" iron pipe standing 1.0 ft. above grade.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-13, T1N, R3E, UNADILLA, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 119 DEG. 6.17' SET NAIL/TAG N/S 8" OAK  
 166 DEG. 29.42' SET NAIL/TAG SW/S 20" OAK  
 221 DEG. 36.16' SET NAIL/TAG W/S 12" OAK(DEAD)  
 094 DEG. 35.86' FD. 1/2" IRON ROD/CAP #24620  
 049 DEG. 17.09' SET NAIL/TAG SE/S 12" ASH

Signed by Darrell D. Hughes  
Surveyor's Michigan License No. 19834

Approved by Liv. Co. Peer Group: Nov. 03, 1993  
Date 12-21-93

UNADILLA TOWNSHIP, TOWN 1 NORTH, RANGE 3 EAST

I-13, SOUTHWEST CORNER, SECTION 35

Field 10-20-93

Found 3/4" iron pipe standing 1.0' above grade. 74' West of centerline Joslyn Lake Rd. (24 ft. wd. gravel). iron lies at toe of slope and 8'+/- below Rd. grade. Wet ground to West. No occupation lines, except at tree row to East, beginning at East side Joslyn Lake Rd. Very evident on 1990 SEMCOG Aerial.

Corner first set by Sylvester Sibley around 1825 coming from the East "on the South boundary of Sec. 35...80.00 chains, set post "...at(edge of) prairie."

1922, Grant Dunning, County Surveyor, "Found stone tipped over in soft ground" Survey No. 129. This stone found from Davis witness'(1878), Dunning identified two new witness trees.

1953, Lyle Munsell, "set 3/4" X 3' pipe 72.7' West of centerline Highway....in line of fence to East." Dunning witness trees gone, stumps O.K." (no mention of stone).

To present, Wilson, Garlock, Benton, Boss, Young have used 3/4" pipe. We did not look for stone.

There is no Act 74 recorded for corner.

I-13UN.DOC