

SURVEY & REMONUMENTATION

FILED

APR 28 1995 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 16 2 00 PM '94

For corners in

COMMISSION

LIVINGSTON
(County)

Located In:

Corner Code =#

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

Public Land Survey	T	<u>1N</u>	R	<u>3E</u>	<u>J-11</u>
	T		R		
	T		R		
	T		R		
Property Controlling in Section	S		T		
	S		T		
Miscellaneous Property in Sec.	S		T		
	S		T		

L.S.C. #342m

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

UNADILLA TWP.

DARRELL HUGHES, in a field survey on NOVEMBER 4, 1994,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- GLO: 1825 Sylvester Sibley, Deputy Surveyor
- White Oak 18" South 88 degrees West 55 links
- White Oak 30" North 55 degrees East 9 links

*Additional historical information on back of sheet

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" smooth iron rod at fence intersection

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11, T1N, R3E, UNADILLA, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 014 DEG. 20.09' SET NAIL/TAG E/S 11" OAK.
- 113 DEG. 19.69' SET NAIL/TAG S/S 13" TWIN OAK.
- 196 DEG. 13.03' SET NAIL/TAG W/S 6" OAK.
- 273 DEG. 37.02' SET NAIL/TAG N/S 21" OAK.

Signed by Darrell Hughes

Date 11-8-94

Surveyor's Michigan License No. 19834



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

REVISED MAY 14, 1975
REVISED JAN., 1983

PEER GROUP ON 17 Nov. 94 CO. REP MBL

I-11, NORTH 1/4 CORNER SECTION 35, T1N, R3E, UNADILLA TWP.

FOUND 1/2" SMOOTH IRON ROD, 1.2' ABOVE GRADE AT N., S., E. AND W. FENCE INTERSECTION THAT I SET IN JANUARY OF 1987 AND FILED AN ACT 74. measured 2651.35' to I-11.

1825 Silvester Sibley, Deputy U.S. Surveyor "set 1/4 sec. post at 40.10 chains (2646.60')".

1838 John Farnsworth, County Surveyor, started survey at this corner. P.8.

1874 Miles Bullock, County Surveyor, measures 40.25 (2655.84') chains to I-11. P.9

1979 Garlock shows corner and measures South to center of Section (2622.79'). No witness'. P.10.

1985 Hughes finds Garlock irons near 1/8 line and copys Garlock measurement north to corner. No witness'. P.11

1987 January, Hughes sets corner at fence intersection and files Act 74. P.12-13.

1987 December, Boss surveys West 1/2 of Section 35, copys Hughes witness'. P.14.

1989 Hughes uses corner in survey. P.15.

Clear to West for GPS, trees to East.