

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Livingston  
(County)

Located In:

Corner Code ##

**FILED**  
**DEC 27 12 22 PM '93**  
 NANCY HAVILLAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843  
 L.S.C. #122m  
 Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>1N</u>	R	<u>3E</u>	<u>K-1</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Darrell D. Hughes, in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825  
 Tamarack 16" S51E 60 lks.  
 Black Ash 6" S41W 39 lks.

SURVEY &  
 REMONUMENTATION  
 1993  
 COMMISSION

\*Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2" steel post 5 ft. high, bent and loose in ground.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1, T1N, R3E, UNADILLA, replaced 1/2" iron rod and 2" steel post with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, at grade, 25' W of E end E/W ditch, 15' S. of CL E/W ditch and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 097 DEG. 41.19' SET 1 1/4" X 36" IRON PIPE/ BRASS DISK FOR SW COR. SEC. 36, T2N, R3E, IOSCO (K-13)  
 058 DEG. 29.54' SET 1" X 36" IRON PIPE/BRASS WIT DISK.  
 010 DEG. 21.97' SET 1" X 36" IRON PIPE/BRASS WIT DISK.  
 324 DEG. 28.77' SET 1" x 36" IRON PIPE/BRASS WIT DISK.  
 WIT. PIPES ARE 9' N OF CL E/W DITCH.

Signed by Darrell D. Hughes  
 Surveyor's Michigan License No. 19834

Date December 27, 1993

STATE OF MICHIGAN  
 DARRELL HUGHES  
 SURVEYOR  
 RECORDED LAND SURVEYING

Approved by Liv. Co. Peer Group: December 11, 1993  
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN. 1983

UNADILLA TOWNSHIP, T1N, R3E

K-1, NORTHWEST CORNER SECTION 1

FIELD 10-27-1993 D.D.HUGHES AND ASSOCIATES, FOWLERVILLE

Found 2" steel post 5' high, bent over and in ground loose. Recorded as 4" post, checks +/- to K-13, Iosco Twp. reset with 1/2" iron rod.

1825, corner first set by Sylvester Sibley, Deputy U.S. surveyor. "intersected North boundary 63 links West of post".

1861, E.N. Fairchilds, County Surveyor, divided Section 36, Iosco Twp.

1876, Miles Bullock, County Surveyor, shows 63 links falling (in wrong direction)

1915, Grant Dunning, County Surveyor, retraced parts of the division of section 36, Iosco.

1965, Lyle Munsell, shows falling (jog) to be 41.19'.

1976, Boss ran extensive traverse for all of Section 36 and into the East 1/2 of Section 35. All corners and 1/4 corners were either found or calculated and given coordinates. 41.19' R&M

1982, Boss shows 4" post for corner with witness'. Witness' now gone.

1990, Hughes found post and witnessed. job no. 90689 (post now bent and witness' are gone)

Corner to be set, based on Boss (1976) section break-down and our surveys in Section 36, Iosco and Sec 2, Unadilla.