

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 1N R 3E K-12
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

FILED
 DEC 22 10 13 AM '93
 NANCY HAVILLAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843
 L.S.C.# 82m
 Register of Deeds Stamp & File Number

I, Darrell D. Hughes, in a field survey on December 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825
 White Oak 22" S81W 202 lks.
 White Oak 12" N55E 302 lks.

* Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" iron rod with cap: No. 14762

D. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12. T1N, R3E, UNADILLA, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.
 220 DEG. 32.19' SET NAIL/TAG SE/S 12" HICKORY
 278 DEG. 31.51' SET NAIL/TAG N/S 12" APPLE
 050 DEG. 17.03' SET NAIL/TAG NW/S 8" ELM
 360 DEG. 29.32' SET NAIL/TAG W/S 6" ELM

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &
 REMONUMENTATION
 1993
 COMMISSION

Signed by [Signature] Approved by Liv. Co. Peer Group: Nov. 03, 1993
 Date 12-21-93

Surveyor's Michigan License No. 19834

UNADILLA TOWNSHIP, T1N, R3E

K-12, EAST 1/4 CORNER SEC. 35

FIELD 10-20-93

Found 1/2" iron rod with cap no. 14762 at grade in wooded area, downed wire running w, n, and s.

Corner first set by Sylvester Sibley on Jan. 15, 1825.

1967, Lyle Munsell, shows corner on survey with distances to cl rd to S. and to SE corner of Section.(2647.68')

1968, Garlock used corner for Kaiser Rd. realignment.

1973, Garlock, reset 1/2" X 18" iron rod, shows 2647.68' to SE corner.

1979, Garlock, reset same and filed Act 74

1987 AND 1991, Boss shows corner on Survey, Liber 1266, P. 855.

Corner is in wooded area 500 feet N. of Kaiser Rd., E. of a mowed foot path, 250' N. of a house.