

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 12 22 PM '93
 NANCY HAVILAND
 REGISTER OF DEEDS
 LIVINGSTON COUNTY, MI
 48843

FILED

For corners in

Livingston
 (County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>1N</u> R <u>3E</u> | <u>L-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

L.S.C. #121m
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Darrell D. Hughes a field surveyor on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO: No original monument set.

SURVEY &
 MONUMENTATION
 1993
 COMMISSION

*Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Physical corner not found.
 Pro-rated measures of existing and computed co-ordinates of corners found and re-measured in Sections 35 & 36.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-1. T1N, R3E, UNADILLA, set corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, 30" below grade in cultivated farm field, 30' E. of cl N/S ditch and is accepted as the best available evidence of the position of the corner. This position was not established by the original government surveyors.
 095 DEG. 20.80' SET 1 1/4" X 36" IRON PIPE/BRASS DISK FOR S 1/4 COR. SEC. 36, T2N, R3E, IOSCO. (L-13)
 210 DEG. 42.52' SET 1" X 36" IRON PIPE/ BRASS WIT. DISK.
 275 DEG. 18.98' SET 1" X 36" IRON PIPE/ BRASS WIT. DISK.
 344 DEG. 41.50' SET 1" X 36" IRON PIPE/ BRASS WIT. DISK.

Signed by Darrell Hughes Date December 27, 1993
 Surveyor's Michigan License No. 19834

Approved by Liv. Co. Peer Group: December 11, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
 1993 REVISED MAY 12, 1975
 REVISED JAN. 1983

UNADILLA TOWNSHIP, T1N, R3E

L-1, NORTH 1/4 CORNER SECTION 1

FIELD 10-27-1993 D.D.HUGHES AND ASSOCIATES, FOWLERVILLE

Corner not found. Location falls in active farm field.
Corner is obliterated but not lost. The corner will be established by retracement of surveys by others.

Corner not originally set by U.S. surveyors.

1861, E.N. Fairchilds, County Surveyor, divided Section 36, Iosco Twp.

1915, Grant Dunning, County Surveyor, retraced parts of the division of section 36, Iosco.

1964, Lyle Munsell, for survey in Northeast 1/4 Section 1, Unadilla, shows relationship of L-13 Iosco and L-1 Unadilla. 20.8' (20.79' is 1/2 falling at Northeast corner Sec. 1) apart and witnessed. No witness' remain now. Book 81, Page 51.

1976, Boss ran extensive traverse for all of Section 36 and into the East 1/2 of Section 35. All corners and 1/4 corners were either found or calculated and given coordinates.

Corner to be set, based on Boss (1976) section break-down and surveys in Section 36 and 35.