

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Livingston  
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>1N</u> R <u>3E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

DEC 22 10 13 AM '93  
 NANCY HAVILLAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843

FILED

L.S.C.# 83m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Darrell D. Hughes, in a field survey on December 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825  
 White Oak 14" N38W 32 lks.  
 White Oak 17" N40E 76 lks.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

REMOVAL

1993

COMMISSION

Additional historical information on back of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 4" diameter concrete monument with 4" diameter aluminum disc. at top

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13, T1N, R3E, left existing conc. monument in place, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 310 DEG. 18.41' SET NAIL/TAG SW/S 12" SHAGBARK HICKORY  
 005 DEG. 16.51' SET NAIL/TAG E/S 14" OAK  
 340 DEG. 11.49' SET NAIL/TAG SW/S 14" CHERRY  
 030 DEG. 65.48' SET NAIL/TAG SE/S 28" OAK  
 190 DEG. 38.59' SET NAIL/TAG W/S 8" ELM (8' ABOVE GRADE)  
 100 DEG. 34.99' SET NAIL/TAG S/S 5" OAK

Signed by Darrell D. Hughes

Approved by Liv. Co. Peer Group: Nov 03, 1993  
 Date 12-21-93

Surveyor's Michigan License No. 19834

UNADILLA TOWNSHIP, T1N, R3E

L-13, SOUTH 1/4 CORNER SEC. 36

FIELD 10-21-93

Found 4" dia. concrete monument with 4" dia. aluminum disc. at top. 6" above grade. Disc stamped (MDNR S 1/4 COR. SEC. 36. T1N,R3E). downed wire fence to N.

Corner first set by Sylvester Sibley, 1825.

1968, corner witnessed by DNR, "fd. 1" pinch pipe using notes of Herald Hamill, Plymouth, Mi."

1980, Don Bissell, DNR surveyor reset pipe with 4" conc. mon. and filed Act 74 for corner.

Corner is at top of slope (20' above lake water grade) at S'ly edge 10 acre island in middle of swamp, 300 ft. N. of N. edge Bruin Lake. Access is from State Campground 2000' to West, use foot path along N'ly shore of Lake.