

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

9  
**FILED**  
**DEC 22 10 13 AM '93**  
 NANCY HAVILLAND  
 REGISTER OF DEEDS  
 LIVINGSTON COUNTY, MI  
 48843

For corners in Livingston (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 1N R 3E M-13  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

L.S.C. # 84m  
 Register of Deeds Stamp & File Number

I, Darrell D. Hughes a field survey on December 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO: 1825  
 Maple 16" N86.5W 28 lks.  
 Ash 14" N14E 58 lks.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Survey &  
 RE-MONUMENTATION  
 1993  
 COMMISSION

\* Additional historical information on rear of sheet:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Fd. 1-1/2" pinch pipe in swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-13. T1N, R3E, UNADILLA, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.  
 100 DEG. 32.73' SET NAIL/TAG S/S 12" TREE (S/S CLUMP OF 5)  
 180 DEG. 38.75' SET NAIL/TAG W/S 10" TREE  
 250 DEG. 26.58' SET NAIL/TAG S/S 10" TREE  
 040 DEG. 17.31' SET NAIL/TAG SE/S TWIN 12" TREE (LEANS 30 DEG. NW)

Signed by Darrell D. Hughes Approved by Liv. Co. Peer Group: Nov. 03, 1993  
 Date 12-21-93  
 Surveyor's Michigan License No. 19834

UNADILLA TOWNSHIP, T1N, R3E

M-13, SE CORNER SEC. 36

FIELD 10-21-93

Fd. 1-1/2'' pinch pipe in swamp under 12" of water . Steel "T" fence post next to iron pipe, also under water. No evidence of occupation except for downed wire fence at shore of swamp, 100' North. Latest witness (1959 Atwell-Hicks) fit existing trees and stumps (+/-). no nails fd.

1925, Grant Dunning, platted "ISLAND LAKE SHORES" subdivision. "...Fd. old stake. set 2" gas pipe, 3' long. S.2E.7" maple (old mark) 13.7'

1959, Atwell-Hicks, Fd. 3/4" pipe badly rusted for SE cor. Sec. 36, Reset with 1" pinch pipe, 120' S. into swamp. steel fence post beside corner.

1967, DNR land cor. record. 1" iron pipe, fd. , this cor recovered using notes from Herald Hamill, Plymouth, Mi.

1986, Atwell-Hicks show corner in survey on Half Moon Lake, Washtenaw Co., same witness' as 1959.

Corner is in Maple swamp, standing water 1'-2' deep with vegetation hillocks and maple trees 10" to 24". corner access is through locked gates on private property, off Patterson Lake Road.