

SURVEY & REMONUMENTATION

FEB 24 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in **SECTION**

LIVINGSTON
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------------|-----------------------------|-------------|
| 1. Public Land Survey | | <u>T 1 N R 4 E</u> | <u>C-13</u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| | | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> | T <u> </u> R <u> </u> | <u> </u> |

1997 NOV 13 P 1:44

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #789m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DARRELL D. HUGHES, in a field survey on NOVEMBER 3, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

PUTNAM TWP.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1825 Sylvester Sibley, Deputy Surveyor
White Oak 20" North 71 degrees West 25 links
Black Oak 21" West 80 degrees East 37 links

* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron pipe in Pine tree farm, 60' ± West of centreline of Glenbrook road, 14.9' West of North/South fence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5, T1N, R4E, PUTNAM, replaced existing corner with 1 1/4" x 36" iron pipe, affixed with 2" dia. Brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 195 deg. Set Nail / Tag E/S 12" Elm 52.95'
- 341 deg. Set Nail / Tag E/S 8" Tree 87.47'
- 007 deg. Set Nail / Tag W/S 6" Walnut 49.09'
- 167 deg. Set Nail / Tag E/S 20" Cherry 85.11'

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 9-3-97 CO. REP JED

Signed by *Darrell D. Hughes*
Surveyor's Michigan License No. 19834

Date NOVEMBER 3, 1997

PUTNAM TOWNSHIP, T1N, R4E

C-13, SOUTHEAST CORNER SECTION 31 AND SOUTHWEST CORNER OF SECTION 32, ON MICHIGAN BASE LINE.

FIELD: 12-16-1996

FOUND 1/2" IRON PIPE IN PINE TREE FARM, 60 FT. WEST OF CL GLENBROOK ROAD, 14.9 FT. WEST OF N/S FENCE. NO PREVIOUS WITNESS' FOUND. PIPE USED IN 1996 LIVINGSTON COUNTY GPS SURVEY. I RECOMMEND TO THE PEER GROUP THE ACCEPTANCE OF THIS PIPE AS THE LOCATION FOR C-13, BASED ON THE EVIDENCE THAT FOLLOWS:

- 1819 Joseph Wampler, U.S. Deputy Surveyor, first set corner on base line, "West on South Boundary of Section 32, 80.00 chains, set post". P.7-7A
- 1849 Lucius Lyon, Surveyor General, compares Fletcher and Wampler base lines, shows 81 chains for South line of Section 32. P.8-8E
- 1945 Clay Gordon surveys and maps lands North and South of base line, shows corner. P.9-9D
- 1948 Michigan Conservation Dept. (DNR) surveys lands, uses corner and identifies as 1/2" pipe. P.10
- 1977 Boss Engineering surveys parcels, North and South of corner, find 1/2" iron pipe. P.11-11C
- 1977 Gary Boss files Act 74, for above surveys. P.12
- 1997 Hughes witness comparisons and field sketch. P.13-13a