

PUTNAM TOWNSHIP, T1N, R4E

E-13, SOUTHWEST CORNER SECTION 33, SOUTHEAST CORNER SEC.32, ON MICHIGAN
BASE LINE.

FIELD: 09-02-1994

FOUND 5/8" IRON ROD IN 12" DIAMETER IRREGULAR CONCRETE (MONUMENT). Corner is Southeast corner of "HI-LAND LAKE SUB. NO.4", L.5, P.4, measures check to other corners of Lot 254 of said plat. Witness' found and measured check with recorded measures. No occupation lines on ground can be seen, however are quite pronounced on aerial. Poor for GPS.

- 1823 Joseph Wampler, U.S. Deputy Surveyor, first set corner on base line. 80 chains from East. (P.7)
- 1849 Lucius Lyon, Surveyor General, compares Fletcher and Wampler base lines and John Mullett's survey South of base line, shows 86 chains for South line of Section 33. (P.8)
- 1869 Miles Bullock finds corner and measures East 2659.80' to F-13. (P.9)
- 1932 "Hi-Land Lake Sub. No.2" platted, tag south to this corner. F.C.Eisenach, Surveyor, Detroit. (P.10)
- 1947 "Hi-Land Lake Sub. No.4" platted, set monument at this corner. Lloyd W. Fall, Surveyor, Detroit. (P.11)
- Date unknown Livingston County Surveyor, base line corner comparison notes. (P.12)
- 1973 Oscar Boss finds monument, shows witness', files Act 74. (P.13-14)
- 1973 Dwyne Scott, files Act 74, makes sketch on back. (P.15)
- 1973 Dwyne Scott, DNR surveyor, shows corner on survey and its relationship with D-1 Dexter Twp., Washtenaw Co. Same distance as shown on "Hi-land Lake No. 4" (P.16)