



PUTNAM TOWNSHIP, T1N, R4E

F-11, 1/4 CORNER COMMON TO SECTIONS 28 AND 33

FIELD: 08-26-1994

Found 1" iron pipe with cap #12032 (Howard Taft, Atwell(-Hicks) 0.8' below gravel drive grade, 11' West of centerline drive, 678' North of centerline Patterson Lake Road. Iron pipe is in N/S fence line, 5' south of E/W walk path. Witness' agree with Taft, Garlock, Boss, and Smith. Sky open to East, blocked by Pines to West. Marginal for GPS.

1823 Corner first set by Joseph Wampler, U.S. Deputy Surveyor. 2656.50' East and West. (P.7)

1972 Howard Taft finds iron pipe and files Act 74. (P.8-9)

1972 William Lincoln finds iron on survey (no witness') (P.10)

1973 Oscar Boss copies Taft Act 74. (P.11)

1975 Ditto (P.12)

1976 Campbell, 3/4" iron pipe, shows new ties for corner in survey. (P.13)

1977 William Lincoln finds iron, no witness', shows bearing and distance to cl Patterson Lake Rd. 678.92' (P.14)

1987 Hughes, in retracement of 1972 Taft survey (P.8), finds iron pipe, no witness', measures distance to found iron pipe (set by Taft) at centerline Patterson Lake Rd. 678.20' (P.15)

1989 Hughes copies Lincoln distance (P.14) (678.92') (P.16)

1991 Garlock witness', finds 1/2" iron rod, shows new tie to Boss iron East 66.03' (P.17)

1992 Smith (Desine) finds 1/2" iron, measures old witness' shows slight difference. (P.18)