

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE

APR 28 1995

Filing Requirement of Act 74, Mich. P.A. 1970

FILED

Nov 16 2 00 PM '94

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C. #348m
Register of Deeds Stamp & File Number

For corners in

LIVINGSTON
(County)

COMMISSION

Corner Code ##

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey | T | <u>1N</u> | R | <u>4E</u> | <u>F-13</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PUTNAM TWP.

I, DARRELL HUGHES, in a field survey on NOVEMBER 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1823 Joseph Wampler, Deputy Surveyor
Black Oak 14" North 14 degrees East 25 links
White Oak 15" North 54 degrees West 37 links

*Additional historical information on back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" iron rod, cap #13574 at East, West and North fence intersection


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass disk. Disk stamped "Livingston Co. Monumentation Corner, 19834" and is accepted as a careful and faithful reestablishment of the position of the original corner.
220 DEG. 9.36' SET NAIL/TAG NW/S 6" OAK.
287 DEG. 13.47' SET NAIL/TAG S/S 6" CEDAR.
054 DEG. 18.21' SET NAIL/TAG SE/S 8" OAK.
128 DEG. 37.52' SET NAIL/TAG SW/S 10" OAK.

Signed by Darrell Hughes

Date 11-8-94

Surveyor's Michigan License No. 19834



P.A. 345 1980, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 28 Sep 94, CO. REP. [Signature]

PUTNAM TOWNSHIP, T1N, R4E

E-13, SOUTH 1/4 CORNER SECTION 33, ON MICHIGAN BASE LINE.

FIELD 09-12-1994

Found 1/2" iron rod with cap No. 13574, Oscar Boss, at E-N-W fence intersection. Poor location for GPS.

1823 Joseph Wampler, U.S. Deputy Surveyor set post 40 chains from East. (P.7)

1849 Lucius Lyon, Surveyor General compares Fletcher and Wampler base lines, also John Mullett's survey of Dexter Twp. Shows south line of Section 33 to be 86 chains (5676'). (P.9)

1869 Miles Bullock finds corner and measures East from E-13 to this corner, 2659.8' (P.8)

1973 Oscar Boss "sets 1/2" iron at fence intersection" and files Act 74. Shows measurement to E-13 (monument at southeast corner of "Hi-Land Lake Sub. No.4") as 2657.41' (P.11-12)