

FILED

OCT 16 11 43 AM '95

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

corners in

<u>LIVINGSTON</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>1N</u> R <u>4E</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

L.S.C. #495m

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

PUTNAM TWP.

DARRELL HUGHES, in a field survey on OCT 4 ~~JANUARY 23~~, 19 95, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO: 1823 Joseph Wampler, Deputy Surveyor
Ash 4" North 82 degrees West 29 links
White Oak 18" South 29 degrees East 35 links

SURVEY &
REMONUMENTATION


NOV 27 1995

COMMISSION

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" iron rod

*Additional descriptions and historical information on back of this sheet.
Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10, T1N, R4E, PUTNAM, replaced existing corner with 1-1/4" X 36" iron pipe, affixed with 2" dia. brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834, and is accepted as a careful and faithful reestablishment of the position of the original corner.
109 DEG. 5.51' FD. 1" PINCH PIPE 0.4' BELOW ROAD GRADE.
233 DEG. 18.96' SET NAIL/TAG SE/S 32" WILLOW.
294 DEG. 27.61' SET NAIL/TAG N/S 34" ASH.
047 DEG. 42.68' SET NAIL/TAG W/S 12" ASH.
141 DEG. 44.87' SET NAIL/TAG SW/S UTILITY POLE.



Signed by [Signature] Date October 5, 1995

Surveyor's Michigan License No. 19834
P.A. 345 1980, APPROVED BY LIVINGSTON COUNTY
PREFR GROUP ON 9-6-95 CO. REP JGD